

Scope of Labor to be provided for Standard Installation

Deliver - Install - Haul Away

- 1) Remove and dispose of old door slab and/or frame
- 2) If a slab, then prep hinges and bore door and/or jamb to match. Salvage slab may be already prepped.
 - May have to use wood putty or caulk to fill in previous preps in door or jamb
- 3) If a slab, then the door may need to be slightly trimmed to fit opening.
 - If major alterations to the door are required, a fee of \$50 or more may be applied to the final quote.
- 4) If PH unit, install door jamb into rough opening and secure and plumb.
 - Secure/caulk threshold to existing floor, jamb and 2x4's.
 - Note that the installer will not caulk door to prepare for paint or stain
 - Adjust brick mould as much as possible to allow for rough opening differences
 - If additional material is needed to adjust for rough opening differences, additional charges will apply
 - If exterior of the home is rock, the installer cannot be responsible for loose rock falling off during install procedure.
- 5) If PH unit, attach new casing on interior side of door if provided by customer at time of install.
 - The installer may not be able to re-install old casing and isn't responsible for old casing after removal

- The installer cannot be responsible for existing interior wall, ceiling conditions, floor or base trim conditions

6) Install standard door hardware, if provided at time of install by customer.

- If using old hardware, the installer cannot be responsible for ensuring the old hardware will work.
- If installing other door hardware, i.e., peephole, kick plate or door numbers, additional charges will apply.

7) If PH unit, re-attach doorbell if available.

- Installer will wire and re-attach doorbell to jamb. But will not wire past door into house.
- Installer can only be responsible for doorbell if it worked previous to install.

8) Adjust door and/or jamb to allow for security contacts or wires

- Note that the installer will not rewire security system and cannot be responsible for contacts working.

9) Make sure the door swings smoothly (unless prohibited by existing obstruction)

10) Installer can re-attach an existing, properly working, storm door or a new storm door for \$100

11) Make sure the door seals properly, weather stripping, door to rough opening, threshold, and sweep

12) Installer to clean up job site after install

13) Other additional labor needed at job site beyond items listed above, will be at an additional charge TBD*

14) Window Installation: Remove wood sashes, track, and stop. Then install new vinyl window. Replace stop, caulk and seal. We cannot be responsible for any damage caused by removing and re-using old stop.

We recommend the customer buys new stop and has it at time of install. We do not re-attach any alarm systems.

Below are not included in Standard Install Pricing

Structural work needed due to rot, termites, other damage. Painting or staining; plaster or drywall. Fixing dents or dings

or scratches that are inherent in buying a surplus and salvage door. Canceling a job to get new materials due

miss-measure/miss-purchase by customer. Creating a new rough opening size.